

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>53</u> N. R. <u>35</u> K. W.	<u>L7, L9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on _____, 19____, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A Description of original monument and accessories and/or subsequent restoration:

Corner L7: Original monument and accessories not found. Found wood post in place. Corner lies one chain north of an old E-W logging road and in a small ravine.

Corner L9: Original monument and accessories not found.

B Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L7: Found wood post set by unknown persons midway between two section corners.

Corner L9: This corner re-established on line between section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L7 and L9 re-established 6/16/66 by Regional Land Surveyor Billy D. Buckler but not recorded.

Corner L7: Set 1" I.D. pipe with 4" aluminum cap.
 13" Red Oak S57°E 23.5 Ft. 1/4S 13/24 NBT
 8" Sugar N61°W 19.0 Ft. 1/4S 13/24 NBT

Corner L9: Set 1" I.D. pipe with 4" aluminum cap.
 8" Y. Birch S37°W 19.2 ft. 1/4S NBT
 7" Y. Birch N35°W 14.0 ft. 1/4S NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

DATE 7/27/36

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

