

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53. NR 34-35 N.

Houghton COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 18-19-13-24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 16" Hard Maple S 2° W 55 links
"S 24° NBT"

15" Hard Maple N 36° E 57 links
"S 18° NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from one yellow birch B.T. bearing S 65° W 20 links in poor condition.

Found two hemlock B.T.s down and in poor condition bearing S 74° E 21 links and N 41° W 47 links.

Corner found by L. Stevens, District Forester.

Placed location poster 9.00 chs. east on road.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 8/12/57
REGISTERED LAND SURVEYOR