

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 35N


Houghton COUNTY

DESCRIPTION OF CORNER Section corner for Sections 27|26

CORNER MONUMENT 1" Iron pipe with 4" brass cap!

DATE MONUMENT PLACED AND WITNESSED 8-22-61

WITNESSES TO CORNER..... 16" Yellow Birch (S27 NBT) N 78°W 37½ links



6" Soft Maple (S26 NBT) N40°E 19 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from hemlock stump 9" N28°E 48 links. Axe marks visible of notch & faces. Hole in position of sugar 10" S42°W 39 links. Stream to south checks well. Stream to west short but may have moved.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 14, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler