

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 35W

Houghton COUNTY

DESCRIPTION OF CORNER Section corner for Sections 26|25


35|36

CORNER MONUMENT 1" iron pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 8-22-61

WITNESSES TO CORNER..... 12" Cedar (S25 NBT) N 62°E 16 links

12" Elm (S25 NBT) N 59°W 32 links



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from cedar 20" N 45°E 10 links, (with scribe marks plainly visible) and 20" Cedar S75°W 28 links, proper distance and bearing but no marks, badly weathered.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 14, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler