

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Houghton Located In: _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|------------|---|------------|---|
| 1. Public Land Survey | T | <u>54N</u> | R | <u>32W</u> | |
| | T | _____ | R | _____ | |
| | T | _____ | R | _____ | |
| | T | _____ | R | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

A-5

MARY SCIDOS 05/05/99 2
HOUGHTON COUNTY, REGISTER 15:00
LC 3/ 597 PAJ Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Ronald S. Haataja in a field survey on August 14, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-5) NW Corner Section 18, T54N-R32W
80.00 Set Post corner of Sections 12, 13 (T54N-R33W)
Witnesses: Maple 10" N48°E 10 lks.
Y. Birch 8" N53°W 23 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-5) NW Corner Section 18, T54N-R32W
Found 2-1/2" pipe 6" above ground.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-5) NW Corner Section 18, T54N-R32W
Stamped and cemented a brass remon. cap into the 2-1/2" pipe
Plastic tags PS#13034 fnd in trees.
7" Balsam S66°E 5.46', 12" Sugar Maple S43°W 7.75',
12" Sugar Maple N05°W 19.52', 8" Sugar Maple N70°E 19.65'

Signed by Ronald S. Haataja Date April 6, 1999
Surveyor's Michigan License No. 39478