

Nov. 6, 1998
 Robert W. Oamptor

DEC 14 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Houghton Located In: _____ Corner Code # _____
 (County)

- 1. Public Land Survey T 54N R 33W (J-7)
 T 54N R 33W Z14
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

ROBERT F. MIKESCH 11/11/98
 HOUGHTON COUNTY, REGISTER 09:40
 LC 3/ 517 PAU Fee: 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

I, Ronald S. Haataja, a field surveyor on August 13, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-7) S 1/4 Corner Section 14, T54N-R33W
 40.00 Set Quarter Section post
 Witnesses: Sugar 12" S56°E 20 lks.
 Yellow Birch 9" N16°W 7 lks.

(Z14) Meander Corner between Sections 14 & 23, T54N-R33W
 74.80 Intersected Lake
 Cedar 4" for Meander Corner
 Witnesses: White Pine 16" N48°E 13 lks.
 Do 18" S28°W 27 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-7) S 1/4 Corner Section 14, T54N-R33W
 Found 3/4" Iron pin w/ flange at top according
 to LCRC Liber 2, Page 475

(Z14) Meander Corner between Sections 14 & 23, T54N-R33W
 Found 1" Drill rod in concrete according to
 LCRC Liber 2, Page 479. Located in front lawn of camp
 with fire # 314



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-7) S 1/4 Corner Section 14, T54N-R33W
 Drove 2" Aluminum pipe over pin and stamped and cemented a brass remon. cap into pipe. Witnesses: Brass tags PS#39478 nailed into side of trees: 9" Balsam N08°W 4.75', 8" W. Birch S73°E 45.39', 4" Maple S24°W 3.89', 7" Maple N87°W 10.05', Fence line to North and South

(Z14) Meander Corner between Sections 14 & 23, T54N-R33W
 Drove drill rod down and stamped and cemented a brass remon. cap inside an 8" iron liner. Witnesses: Brass tags PS#39478 nailed to trees: NE Cor Hse S85°E 23.25', NW Cor Hse South 18.13', 12" Oak S77°W 16.75', 14" Maple N09°E 8.13', 15' to water's edge.

Signed by Ronald S. Haataja Date November 6, 1998

Surveyor's Michigan License No. 39478