

Nov. 6, 1998
Robert W. Campbell

SURVEY &
 MONUMENTATION

DEC 14 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Houghton Located In: 35 Corner Code # _____
 (County)

1. Public Land Survey T 54W R 33W _____ J-13
 T _____ R _____
 T _____ R _____ *Seg #1 NW*
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

ROBERT F. MIKESCH 11/11/98
 HOUGHTON COUNTY, REGISTER 09:43
 LC 3/ 526 PAU Fee: 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert A. Goodreau in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:
 J-13 Post Set - 1845 by D. Houghton
 Cedar, 12", N65°E, 40 LKS
 Fir, 10", N12°W, 31 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J-13 Nothing found. Corner was set by using single proportion method between west corner Section 35 and east corner Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-13 Set 1" galvanized pipe, 2" brass remon cap in approx. centerline of Co. Rd. T-1641. Witness set with 60d nail, brass "UPEA" tags, chest blaze.
 Hemlock, 9", SCR. NBT N24°W, 58.19'
 Balsum Fir, 9", SCR. NBT, N31°E, 51.46'
 Balsum Fir, 8", SCR. NBT, S33°E, 37.70'
 Balsum Fir, 11", SCR. NBT, S28°W, 33.25'

Signed by *R.A. Goodreau*
 Surveyor's Michigan License No. 43053

Date *Oct*

