

Houghton County
 Nov. 6, 1998
 Robert W. Camp

DEC 14 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Houghton Located In: Corner Code #
 (County)

ROBERT F. MIKESCH 11/11/98
 HOUGHTON COUNTY, REGISTER 09:41
 LC 3/ 519 PAU Fee: 9.00
 Page 1 of 1

- 1. Public Land Survey T 54N R 33W K-7
 T 54N R 33W L-7
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, Ronald S. Haataja, in a field survey on August 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K-7) SW Corner Section 13, T54N-R33W
 80.00 Set post corner of Sections 13, 14, 23, 24
 Witnesses: Hemlock 24" S34°W 9 lks.
 Yellow Birch 10" N71°E 24 lks.

(L-7) S 1/4 Corner Section 13, T54N-R33W
 40.03 Set Quarter Section post
 Witnesses: Fir 10" N54°W 31 lks.
 Do 10" S77°E 10 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K-7) SW Corner Section 13, T54N-R33W
 Found 1/2" pin in centerline of Johnson Road
 at fence line to West

(L-7) S 1/4 Corner Section 13, T54N-R33W
 Found 1 1/2" pipe 12" above ground near aluminum Quincy Mining Co. Tag in tree and old barb wire fence to North and South and 0.9' from face of 24" Maple w/ barb wire

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K-7) SW Corner Section 13, T54N-R33W
 Drove 1 1/2" pipe over 1/2" pin and stamped and cemented a brass remon. cap into pipe
 Witnesses: Brass tags PS#39478 nailed into side of trees
 4" W. Birch N47°E 34.53', 7" Oak S66°E 27.21',
 20" W. Pine S80°W 45.60', Utility Pole N21°W 83.42

(L-7) S 1/4 Corner Section 13, T54N-R33W
 Accepted the pipe as the corner, Stamped and cemented a brass remon. cap into pipe. Witnesses: Brass tags PS#39478 nailed into side of trees: 6" Hemlock N21°E 30.91', 12" Maple w/QMC tag S74°E 11.14', 12" Maple S6°W 44.69', 4" Hemlock N27°W 6.33'.

Signed by Ronald S. Haataja Date November 6, 1998
 Surveyor's Michigan License No. 39478

