

DEC 14 1998

APPROVED BY
Houghton County

Nov. 6, 1998
Ronald W. Haataja

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Houghton
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 54N R 33W
T 54N R 33W
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

K-7
L-7

ROBERT F. MIKESCH 11/11/98
HOUGHTON COUNTY, REGISTER 09:41
LC 3/ 519 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		9		9		10		11		1
5											
6	18		17		16		15		14		1
7											
8	19		20		21		22		23		2
9											
10	30		29		28		27		26		2
11											
12	31		32		33		34		35		3
13											

I, Ronald S. Haataja in a field survey on August 18, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(K-7) SW Corner Section 13, T54N-R33W
80.00 Set post corner of Sections 13, 14, 23, 24
Witnesses: Hemlock 24" S34°W 9 lks.
Yellow Birch 10" N71°E 24 lks.

(L-7) S 1/4 Corner Section 13, T54N-R33W
40.03 Set Quarter Section post
Witnesses: Fir 10" N54°W 31 lks.
Do 10" S77°E 10 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(K-7) SW Corner Section 13, T54N-R33W
Found 1/2" pin in centerline of Johnson Road
at fence line to West

(L-7) S 1/4 Corner Section 13, T54N-R33W
Found 1 1/2" pipe 12" above ground near aluminum Quincy Mining Co. Tag in tree and old barb wire fence to North and South and 0.9' from face of 24" Maple w/ barb wire

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(K-7) SW Corner Section 13, T54N-R33W
Drove 1 1/2" pipe over 1/2" pin and stamped and cemented a brass remon. cap into pipe
Witnesses: Brass tags PS#39478 nailed into side of trees
4" W. Birch N47°E 34.53', 7" Oak S66°E 27.21',
20" W. Pine S80°W 45.60', Utility Pole N21°W 83.42

(L-7) S 1/4 Corner Section 13, T54N-R33W
Accepted the pipe as the corner, Stamped and cemented a brass remon. cap into pipe. Witnesses: Brass tags PS#39478 nailed into side of trees: 6" Hemlock N21°E 30.91', 12" Maple w/QMC tag S74°E 11.14', 12" Maple S6°W 44.69', 4" Hemlock N27°W 6.33'.

Signed by Ronald S. Haataja Date November 6, 1998

Surveyor's Michigan License No. 39478

