

Nov. 6, 1998
Robert W. Coampter

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 54N R 33W M-5
T 54N R 33W Z12(U)
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

ROBERT F. MIKESCH 11/11/98
HOUGHTON COUNTY, REGISTER 09:37
LC 3/ 513 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Ronald S. Haataja, in a field survey on August 14, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-5) NE Corner Section 13, T54N-R33W
80.00 Set post corner of Sections 12 & 13
Witnesses: Maple 10" N48°E 10 lks.
Y. Birch 8" N53°W 23 lks.

(Z12) Meander Corner between Sections 12 & 13, T54N-R33W
34.05 Intersected Portage Lake, Set meander post
Witnesses: Cedar 6" S6°E 8 lks.
Hemlock 9" S80°E 25 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-5) NE Corner Section 13, T54N-R33W
Found 2 1/2" Pipe 6" above ground

(Z12) Meander Corner between Sections 12 & 13, T54N-R33W
Nothing found, Set 1 1/2" pipe on top of bank on a bearing from the NE Corner of Section 13 based on a survey by J.I.Haataja dated 7/16/88.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-5) NE Corner Section 13, T54N-R33W
Stamped and cemented a brass remon. cap onto pipe
Witnesses: Plastic tags PS#13034 fnd in trees
7" Balsam S66°E 5.46', 12" Sugar Maple S43°W 7.75',
12" Sugar Maple N05°W 19.52', 8" Sugar Maple N70°E 19.65'

(Z12) Meander Corner between Sections 12 & 13, T54N-R33W
Stamped and cemented a brass remon. cap into pipe
witnesses: Brass tags PS#39478 nailed into side of trees
20" Ash N87°W 16.22', 6" Poplar N32°W 7.50',
7" Cherry N02°W 11.03', 5" Maple N21°E 20.55',
32' to water's edge

Signed by Ronald S. Haataja Date November 6, 1998

Surveyor's Michigan License No. 39478

