

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|-------------------------|----------|
| 1. Public Land Survey | T 55N R 31W | MC C5-C6 |
| | T 55N R 31W | C6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 12 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (MC C5-C6) Meander Corner between Sections 17-18, North of 1/4 corner. Previously re-monumented by Billy D. Buckler RLS in 1965: 1" pipe with 4" aluminum cap. 8" W. Birch S18W 59.4', 4" W. Spruce N68W 8.4'.
 (C6) Quarter corner common to Sections 17-18. Corner reestablished in 1965 by Billy D. Buckler RLS. 1 1/4" iron pipe buried. 12" W. Pine S70E 40.6', 11" W. Pine S05E 34.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC C5-C6) Recovered the 1965 monument at record bearing and distance from the 1965 witnesses, the birch in good condition with overgrown blazes and the spruce in good condition with no markings evident. An old squared and scribed cedar post was found adjacent to the monument. I left the monument in place and marked new witnesses as described below. No land survey was made here this date. The monument is at a tree line east of a marsh. From the monument, the lake shore is West approx. 100'.
 (C6) Recovered the 1965 monument as described. The monument is in a swamp and it's top is covered with about 12" of water. The decaying stump remains of the 1965 witnesses were recovered at record bearing. Their distances were transposed on the 1965 record. I left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: (MC C5-C6) Found 1" ID iron pipe with 4" alum. cap. Blazed and scribed the following: 6" B. Spruce S13E 6.8' 5" B. Spruce S39W 60.8' 6" W. Spruce N61W 8.4' 9" W. Birch (E'ly in clmp) S22W 59.4' (the 1965 NBT) with overgrown blazes. Set a sq'd spruce post adjacent. Bearings are magnetic. Dist. to notch in lower blaze.	(C6) Found 1.25" ID iron pipe. Blazed and scribed: 6" W. Pine N81W 46.7' 12" W. Pine West 46.9' 5" W. Pine S67W 68.1' 6" W. Pine S51W 83.6' Placed a sq'd spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	"MC NBT" do do "1/4S NBT" do do
---	--	--



Signed by Stephan J. Szyszkoski Date 8/15/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division