

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

RICE LAKE ACCESS

T. 55 N.R. 31 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 19-20

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/20/65

WITNESSES TO CORNER..... 9" Red Pine (1/4S NBT), S 66° W, 22 lks.



9" Red Pine (1/4S NBT), N 5° E, 24 1/2 lks.

Placed Location Poster 1 1/2 chains South of Corner on Road

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner replaced from one Y. Pine stump, S 17° W, 60 lks. as probable bearing tree. Found old blazes in vicinity. Position fits streams and swamp edges to North.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE _____
REGISTERED LAND SURVEYOR