

JAN 09 1998

*Robert W. Crampton*  
DEC 10, 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

HOUGHTON

(County)

Located In:

Corner Code #

NANCY FENILI 12/11/97

HOUGHTON COUNTY

11:20

LC 3/ 444 PAU Fee: 9.00

Page 1 of 1

1. Public Land Survey

T 55N R 32W

(D9)  
E10

T 55N R 32W

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

November 20, 1997

I, Steven C. Hein, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

(D9) From Original Notes: 40.00 Set qr. Section post; Hemlock 10 S10E 15; Y. Birch 9 S32W 39. No evidence of original corner. Corner was accepted by Robert W. Crampton, P.S. 24591 in a November 12, 1991 survey and recorded by him in Liber 1 of L.C.R.C., page 897.  
(E10) From Original notes: 40.00 Set qr. Section Post; Sugar 16 S59E 17; Yellow Birch 12 N76E 04. No evidence of original corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) Found 1" pipe at fence intersection - East, West and South. Found witnesses: 10" Cedar S72W 17.08' (16.80' meas.); 8" Balsam (dead and down) S51W 27.33'; 4" W. Birch S22W 21.0' (20.97' meas.); 10" Balsam S89E 38.10' (37.95' meas.). Replaced 1" pipe with Houghton County Remonumentation brass cap.  
(E10) Found 3/4" square pin on Westerly road R/W as evidence of quarter corner location, but it's position did not fit straight line or proration. Set Quarter Corner on line between and equidistant from found Section corners to North and South. Corner position falls 7' East of Mud Lake Road centerline. Set Houghton County Remonumentation brass cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Set 2 1/4" Brass cap on 3/4" pipe  
New Witnesses:  
5" W. Birch S89E 14.77'  
4" R. Maple S22W 19.10'  
6" Spruce S51W 10.60'  
4" W. Birch N78W 40.82'  
Witnesses have nail & tag #32336

(E10) Set 2 1/4" Brass cap on 3/4" pipe, 6" below gravel road surface  
Witnesses:  
11" H. Maple N46E 40.58'  
9" H. Maple S71E 41.18'  
3/4" Sq. pin N83-07-32W 41.33'  
6" R. Maple N55W 65.83'  
Witnesses have nail & tag #32336



Signed by *Steven C. Hein*  
Surveyor's Michigan License No. 32336

Date Nov. 23, 1997