

Ronald W. Haataja
DEC. 10, 1997

**SURVEY &
REMONUMENTATION**

JAN 09 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 55 NR 32 W E-1
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

NANCY FENILI 12/11/97
HOUGHTON COUNTY 11:24
LC 3/ 456 PAU Fee: 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald S. Haataja, in a field survey on November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-1 North between Sections 4&5
79.90 Intersected South Boundary of
Township 56N at corner of Sections 32&33
Sugar 10 S11E 25
Do 13 S40W 41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-1 No evidence of original survey found.
I found an old fence intersection at the Section corner location a measured distance of 2635.72 feet from the East 1/4 corner of Section 5.

I accepted the fence intersection as the Section corner and remonumented the corner by setting an 1 1/4" Iron pipe at the fence Intersection and cemented in a brass remonumentation cap stamped:
T56-R32
S32 | S33
S5 | S4
T55-R32
1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-1 The 1 1/4" O.D. pipe was witnessed with brass survey tags PS39478 nailed to:
12" Maple N40°E 18.35'
6" Maple S83°E 30.82'
8" W. Birch South 7.50'
2 1/2" W. Pine West 21.60'



Signed by Ronald S. Haataja

Date November 25, 1997

Surveyor's Michigan License No. 39478