

JAN 09 1998

SECTION

APPROVED LAND CORNER
P.A. 345 OF 1990
Houghton County

Ronald S. Haataja
DEC 10, 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 55N R 32W
T 55N R 32W
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

E-2
E-4

NANCY FENILI 12/11/97
HOUGHTON COUNTY 11:23
LC 3/ 452 PAU Fee: 11.00
Page 1 of 2

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald S. Haataja field survey on October, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-2) E 1/4 Cor. Section 5, T55N-R32W
40.00 set qr. post Sugar 10" S64°W 37 lks.
Do 6" N55°E 17 lks.

(E-4) E 1/4 Cor. Section 8, T55N-R32W
40.00 set qr. post Hemlock 10" N73°W 10 lks.
Ironwood 9" N50°E 12 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-2) E 1/4 Cor. Section 5, T55N-R32W
Found 2" O.D. Pipe according to C.E. Hein Survey SMI
Vol. 1, page 431

(E-4) E 1/4 Cor. Section 8, T55N-R32W
Found 3/4" iron pipe according to J.I. Haataja survey
map Vol. 1, page 487



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-2) E 1/4 Cor. Section 5, T55N-R32W 2" O.D. pipe fnd. 1' B.G.
Witnesses: Util. Pole with tag #39478 N31°E 33.06', Util.
Guy Pole with tag #39478 S89°E 22.66', 4" Apple with tag #
39478 S06°E 33.14', 6" Poplar with tag #39478 S63°W 26.50',
Approx. P.I. of Giacioletto Road.

(E-4) E 1/4 Cor. Section 8, T55N-R32W Fnd. 3/4" iron pipe
Witnesses: 12" Oak with tag # 39478 N45°E 5.97', 4" Maple
with tag #39478 S54°E 7.58', 10" Maple with tag #39478 S33°W
12.14', 3" Maple with tag #39478 S84°W 16.65'.
See back for remon. cap details.

Signed by Ronald S. Haataja Date November 25, 1997

Surveyor's Michigan License No. 39478

3-452
LC

(E-2) E1/4 Cor. Section 5, T55N-R32W 2" O.D. Pipe found
Cemented brass remon. cap into pipe and stamped T55N-R32W
1/4 $\frac{4}{5}$ cor
1997

(E-4) E1/4 Cor. Section 8, T55N-R32W 3/4" iron pipe found
Cemented brass remon. cap into pipe and stamped T55N-R32W
1/4 $\frac{8}{9}$ cor
1997

1912 3 12 13