

APPROVED LAND CORNER
P.A. 345 OF 1990
Houghton County

Ronald S. Haataja
DEC 10, 1997

SURVEY &
REMONUMENTATION

JAN 09 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Houghton
(County)

Located In:

Corner Code #

NANCY FENILI 12/11/97
HOUGHTON COUNTY

11:23
9.00
Page 1 of 1

- | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>55N</u> | R | <u>32W</u> | <u>E-3</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3				•									
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	20		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald S. Haataja, in a field survey on October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-3) Wm. Ives marked a 6" Cedar as the corner in 1946.
References: 7" Fir N19°E 191ks., 16" Hemlock S10°W 271ks.
No trace of original corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-3) Found according to LCRC 601 Vol. 1



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-3) Found 1" sq. iron bar
Witnesses: 10" Sugar Plum with tag #39478 S10°W 2.03', 4" Sugar Plum with tag #39478 N03°E 17.28', 10" Maple with tag #39478 N35°E 25.75', 4" Spruce with tag #32336 S60°E 7.83', Creek 66' West
Remonumented by driving 1" I.D. Pipe over the 1" iron bar and cemented brass remon. cap onto pipe and stamped

T55-R32

5 | 4
8 | 9

1997

Signed by Ronald S. Haataja

Date November 25, 1997

Surveyor's Michigan License No. 39478