

Ronald S. Haataja
Oct. 28, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

For corners in
Houghton
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 55N R 33W A-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Mary Schoos IP
Register of Deeds
Houghton County, Register
Page 1 of 1 LC 4/60
PAU Date 12/30/1999 Time 10:47:44
9.00

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Ronald S. Haataja in a field survey on April, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(A-7) SW corner Section 18, T55N-R33W
80.00 Set post corner of Sections 13 & 24 (T55N-R34W)
References: Sugar 16" S40°W 43 lks.
Do 14" N26°W 46 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(A-7) SW corner Section 18, T55N-R33W
Found 1" o.d. pipe 25' South of Road centerline with
Witnesses by P.S. # 19833

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(A-7) SW corner Section 18, T55N-R33W
Cemented a Brass Houghton County Remonumentation cap onto
found 1" o.d. pipe
Witnesses: P.S. # 19833
3" Ironwood S80°E 12.18'
12" Oak S02°E 26.68'
8" Maple S42°W 22.05'
6" Ash N35°W 57.89'



Signed by Ronald S. Haataja

Date October 20, 1999

Surveyor's Michigan License No. 39478