

JAN 25 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey

T	<u>55N</u>	R	<u>33W</u>	
T	<u>55N</u>	R	<u>33W</u>	<u>1-8</u> ✓
T	_____	R	_____	<u>14 (1/3-9)</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
- 2. Property Controlling in Section

S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
- 3. Miscellaneous Property in Section

S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

MARY SCHOOLS 09/27/99
HOUGHTON COUNTY, REGISTER 10:12
LC 4/ 32 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

I, R.W. CRAMPTON, in a field survey on APRIL 27, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		2		
5													
6	18		17		16		15		14		3		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1-8, SET QR. SECTION POST, SUGAR 14 N9E 21, HEMLOCK 30 S69W 16.
- 14, SET MEANDER COR. POST, FIR 12 S52W 43.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1-8, SET 1" IRON PIPE WITH BRASS CAP ON LINE AND MIDWAY BETWEEN THE NORTHWEST CORNER AND SOUTHWEST CORNER OF SECTION, 10' EAST AND 50' SOUTH OF PAINT LINE.
- 14, SET 1" IRON PIPE WITH BRASS CAP, ON LINE BETWEEN SOUTHWEST CORNER AND SOUTHEAST CORNER BETWEEN MONUMENTS IN ASSESSOR'S PLAT OF MASON. LOT 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1-8, THE 1" IRON PIPE WAS WITNESSED WITH SURVEY TAG NAILED TO:
7" POPLAR TREE N60°W 29.35', 6" MAPLE TREE N05°W 23.70',
7" OAK TREE S19°E 37.91', 7" W. PINE TREE S43°W 43.25'.
- 14, THE 1" IRON PIPE WAS WITNESSED WITH SURVEY TAG NAILED TO:
4" W. BIRCH TREE N47°E 26.60', 4" POPLAR TREE S47°E 87.62',
6" POPLAR TREE N67°W 28.96', S42°W 87.19' TO NW COR. HOUSE S35°39'41"E
25.49' TO PLAT MONUMENT, N35°39'41"W 99.26' TO PLAT MONUMENT.



Signed by Robert W. Crampton
Surveyor's Michigan License No. 24591

Date SEPT. 9, 1999