

JAN 25 2000

Robert W. Crampton
9/24/99

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|------------|----------------|
| 1. Public Land Survey | T | <u>55N</u> | R | <u>33W</u> | <u>1-9</u> ✓ |
| | T | <u>35N</u> | R | <u>33W</u> | <u>7(LM-5)</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

MARY SCHOOS 09/27/99
HOUGHTON COUNTY, REGISTER 10:11
LC 4/ 30 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R.W. CRAMPTON, in a field survey on MAY 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1-9, SET POST COR OF SEC, SUGAR 10 N87E 26, MAPLE 9 S21W 20.
7, LAKE, SET MEANDER COR. POST, FIR 14 S67W 28.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1-9, 1" IP (FND) FROM DIMENSION SHOWN ON THE PORPOSED ASSESSOR'S PLAT OF MASON. SET 2 1/4" BRASS CAP.
7, SET 1/4" IRON PIPE WITH BRASS CAP, ON THE NORTH LINE OF THE PLAT OF TAMARAC CITY. (PLAT CABINET 1, FOLIO 27), ON THE EASTERLY RIGHT OF WAY LINE OF PINE STREET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1-9, THE 1" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
9" MAPLE TREE N20°W 110.39', UTILITY POLE N33°E 77.15'.
8" MAPLE TREE S61°W 71.25', 5" OAK TREE S73°W 30.43'.
7, THE 1" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
TWIN 10" W. BIRCH TREE N30°E 7.40', 6" BOX ELDER TREE S65°E 27.79',
N86°W 100.70' TO 1/2" ROD W/CAP (S. HEIN), N65°W 11.55' TO 1/2" ROD W/CAP (R. HAATAJA).

Signed by *Robert W. Crampton*
Surveyor's Michigan License No. 24591

Date SEPT. 23, 1999