

JAN 25 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 55N R 33W
T 55N R 33W
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

K-5
L-5 ✓

MARY SCHOOS 09/27/99 2
HOUGHTON COUNTY, REGISTER 10:11
LC 4/ 28 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, R.W. CRAMPTON, in a field survey on AUGUST 20, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-5, COR. OF SECTS. 11, 12, 13, 14, W. PINE 16 N19W 16, HEMLOCK 12 S66E 21.

L-5, SET QR. SECTION POST, HEMLOCK 9 N48W 17, YELLOW BIRCH 12 S54E 27.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5, 1 1/2" IRON PIN FOUND FROM OLD MINING COMPANY NOTES, 70+/- DOWN FROM TOP OF BANK OF HUNGARIAN FALLS.

L-5, 1" IRON PIPE IN 1.5' DIA CONC., FROM THE FIRST ADDITION TO NELLONSVILLE, PLAT CABINET 1, FOLIO 76.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5, THE 1" PIN WAS WITNESSED WITH SURVEY TAG NAILED TO:
6" HEMLOCK TREE N08°W 7.53', 36" HEMLOCK TREE N36°E 10.13',
16" HEMLOCK TREE S12°W 16.04', 11" Y. BIRCH TREE N64°W 5.94'.

L-5, THE 1" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
23" W. PINE TREE N21°W 12.29', 6" POPLAR TREE S73°E 19.84',
6" POPLAR TREE S37°E 15.66', 6" POPLAR TREE S34°W 18.90'.

Signed by Robert W. Crampton

Date SEPT. 23, 1999

Surveyor's Michigan License No. 24591