

Houghton Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Table with 3 columns: FOR CORNERS OF-, LOCATED IN-, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-26, 4-27 & 5-3, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

Corner 16: Found 2 1/2" I.D. Iron Pipe which seems to fit with other corners in area.
Corner C3: Original monument and accessories not found. Found 1" I.D. by unknown length iron pipe buried in west edge county road in line with fences south and east.
Corner C1: Original monument and accessories not found. Found 1" iron pin buried in N-S county road in line with fence west and road east.
Corner E4: Original monument and accessories not found. Found 1 3/4" I.D. by unknown length iron pipe at fence corner N-S-W east fence 59 ft. north.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 16: Re-established 5-3-78 at pipe.
Corner C3: Re-established 4-26-78 at pipe.
Corner C1: Re-established 4-27-78 at iron pin.
Corner C4: Re-established 4-27-78 at iron pipe. Doesn't fit very good for latitude, but apparently has been used as corner. Does not fit with old fence east also.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 16: 2 1/2" I.D. Iron Pipe 2 ft. high of unknown length. DNR tag and nail in: 9" Cedar S07E 25.15 ft. 8" Cedar S42W 33.78 ft.
Corner C1: 1" by unknown length Iron Pin DNR tag and nail Yellow post N89W 26.96 ft. Power pole S56W 41.78 ft. Tele. junc. box S35E 50.4 ft.
Corner C3: 1" I.D. by unknown length Iron Pipe buried in west edge county road. Marker Post for underground telephone cable S52E 49.3 ft. Stop sign S09W 90.8 ft.
Corner E4: 1 3/4" by unknown length Iron Pipe at N-S-W fence corner. Nail in: 5" Maple S84W 15.15 ft. 6" Maple South 15.65 ft. DNR tag and nail: 6" Maple N01E 15.34 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett, MICHIGAN REGISTERED LAND SURVEYOR, Department of Natural Resources. DATE July 11, 1978. (SEAL) KEITH L. SACKETT LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006