

Houghton Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 55 N. R. 33 W. E5, E3, D3
2. PROPERTY CONTROLLING IN SECTION T. N. S. R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 27, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner E5: Original monument and accessories not found. Found boat spike in airport road apparently set during airport renovation.
Corner E3: Original monument and accessories not found. Found 1 3/4" I.D. Iron Pipe and old scribed post at Int. of fence lines.
Corner D3: Original monument and accessories not found. Found 3/4" reinforcement rod in fence line E-W.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner E5: Re-established 4-27-78 corner at boat spike.
Corner E3: Re-established 4-27-78 at iron pipe.
Corner D3: Re-established 4-27-78 at rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner E5: Boat spike set in Houghton County Airport Road. DNR reference tag and nail in: 12" Cedar S29W 64.68 ft. 10" Cedar S53E 121.23 ft.
Corner D3: 3/4" reinforcement rod DNR tag and nail in: Power pole west 9.60 ft. 4" cedar N43W 39.52 ft. 4" cedar S62W 30.43 ft.
Corner E3: 1 3/4" I.D. Iron Pipe at intersection of fence lines. DNR tag and nail in: 4" Cedar S57E 34.12 ft. 5" Maple N08W 23.40 ft. Steel bar with mushroom top S34W 5.9 ft.

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY DATE

APPROVED AND SIGNED BY Keith L. Sackett, MICHIGAN REGISTERED LAND SURVEYOR, Department of Natural Resources, DATE July 7, 1978 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006