

Ronald W. Haataja
OCT 28 1999

JAN 25 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Houghton Located In: Corner Code #
(County)

- 1. Public Land Survey T 55N R 34W I-8
T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
Mary Schoos 1P
Register of Deeds
Houghton County, Register
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___ Page 1 of 1 LC 4/64
Miscellaneous S ___ T ___ R ___ PAU Date 12/30/1999 Time 10:52:01
Property in Section S ___ T ___ R ___ FFF- 9.000

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Ronald S. Haataja a field survey on November, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(I-8) West Quarter corner Section 23, T55N-R34W
40.00 Set Quarter Section post
References: Cedar 12" N32°E 9 lks.
Sugar 8" S49°W 39 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(I-8) West Quarter corner Section 23, T55N-R34W
Found 1/2" iron pin in 2'x2' ~~xxxxxx~~ concrete (dated 8-23-20)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(I-8) West Quarter corner Section 23, T55N-R34W
Accepted the pin in concrete as the corner. Drilled hole in concrete and set Brass Houghton County Remonumentation cap over pin.
Witnesses: Brass Tags PS#39478 nailed into side of trees
6" White Pine S09°E 13.85'
20" Maple N78°E 16.72'
3" Maple S85°W 24.73'
6" White Birch N11°W 32.46'

Signed by Ronald S. Haataja
Surveyor's Michigan License No. 39478

Date October 20, 1999