

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 09 1998

SEPT. 23, 1997
Robert W. Crampton
For corners in
HOUGHTON
(County)

Located In: _____ Corner Code # _____

SECTION

- | | | | | | |
|--------------------------------------|---|------------|---|------------|-------------------|
| 1. Public Land Survey | T | <u>55N</u> | R | <u>34W</u> | <u>I-10, I-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

NANCY FENILI 09/23/97 #
HOUGHTON COUNTY 14:36
LC 3/ 434 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

I, R. W. CRAMPTON, in a field survey on SEPTEMBER 8, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 ORIGINAL POST OR ACCESSORIES NOT FOUND. 1/4 CORNER BETWEEN SECTION 27 & 26.

I-11 ORIGINAL POST OR ACCESSORIES NOT FOUND. SECTION CORNER COMMON TO SECTION 27, 26, 34 & 35.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 1" O.D. IRON PIPE IN MONUMENT BOX @ INGOT & ELEVATION STS. REPLACED WITH 1/2" IRON PIPE WITH 2 1/4" BRASS CAP. PREVIOUSLY RECORDED BY BRIAN R. TAAVOLA, LIBER 2, PAGE 535.

I-11 FOUND COPPER CLAD ROD SET MONUMENT BOX. SET 3/4" IRON PIPE WITH 2 1/4" BRASS CAP OVER ROD IN MONUMENT BOX. PREVIOUSLY RECORDED BY BRIAN R. TAAVOLA, LIBER 2, PAGE 537.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*I-10 1/2" IRON PIPE WITH BRASS CAP, WITNESSED WITH SURVEY TAG NAILED TO:
POWER POLE N50°W 41.24', P.K. IN 3" MAPLE TREE N38°E 66.87',
P.K. NAIL S18°E 100.69', S63°W 64.75' TO CENTER WATER VALVE COVER.*

*I-11 3/4" IRON PIPE WITH BRASS CAP, WITNESSED WITH SURVEY TAG NAILED TO:
POWER POLE S05°E 41.62', STEEL FENCE CORNER AT GROUND N60°W 71.55',
CORNER CONC. BLK GAS STATION N75°E 51.77', NE CORNER CONC. PORCH S45°E 77.11'.*



Signed by *Robert W. Crampton*
Surveyor's Michigan License No. 24591

Date Aug. 26, 1997