

Ronald W. Haataja
Oct. 28, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

For corners in
Houghton
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 55N R 34W
- T ___ R ___
- T ___ R ___
- T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
- in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
- Property in Section S ___ T ___ R ___

J-7

_____ Mary Schoos

_____ Register of Deeds

_____ Houghton County, Register

_____ Page 1 of 1

_____ PAJ Date 12/30/1999 Time 10:53:51

_____ FEE: _____

1P

Register of Deeds

Houghton County, Register

Page 1 of 1 LC 4/66

PAJ Date 12/30/1999 Time 10:53:51

FEE: _____ 9.00

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		38	
13												

Ronald S. Haataja in a field survey on September 15, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-7) North Quarter corner Section 23, T55N-R34W
39.60 Set Quarter Section Post
References: Maple 12" N78°W 9 lks.
Sugar 9" S67°E 26 lks.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-7) North Quarter corner Section 23, T55N-R34W
No evidence of original corner or accessories found.
Set 1" Hex Drill Rod with bit at top from proportioning the distance between the Northwest and the Northeast corners of Section 23, T55N-R34W.
Set during a field survey on September 15, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-7) North Quarter corner Section 23, T55N-R34W
Replaced the 1" Hex Drill Rod with a 1-1/2" Iron Pipe and cemented on a brass Houghton County Remonumentation cap
Witnesses: Brass Tags PS#39478 nailed into side of trees.
7" Poplar S23°W 68.38'
10" Jack Pine N22°E 36.52'
6" White Birch S85°E 53.44'
10" Jack Pine S49°E 3.23'

Signed by Ronald S. Haataja

Date October 20, 1999

Surveyor's Michigan License No. 39478