

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 09 1998

SEPT. 23, 1997.
Robert W. Crampton

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey
 - T 55N R 34W
 - T 54N R 34W
 - T _____ R _____
 - T _____ R _____
- 2. Property Controlling in Section
 - S _____ T _____ R _____
 - S _____ T _____ R _____
- 3. Miscellaneous Property in Section
 - S _____ T _____ R _____
 - S _____ T _____ R _____

(K-13 L-13)
L-1

NANCY FENILI 09/23/97 #
HOUGHTON COUNTY 14:34
LC 3/ 430 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. W. CRAMPTON, in a field survey on AUGUST 9, 1997
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 SET POST CORNER SECTIONS 35 AND 36, HEMLOCK 7, N38E 18, HEMLOCK 7 N14W 17.
L-13 55-34 & L-1 54-34 BIRCH 6 QR. SECTION CORNER, BIRCH 6 N40E 27.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 1/2" IRON PIPE FOUND, REPLACED WITH 1" IRON PIPE WITH 2 1/4" BRASS CAP.
L-13 55-34 & L-1 54-34 1" IRON PIN IN MONUMENT BOX FOUND, SET 1" IRON PIPE WITH 2 1/4" BRASS CAP OVER 1" PIN.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*K-13 THE 1" IRON PIPE WITH BRASS CAP WITNESSED WITH SURVEY TAG NAILED TO:
UTILITY POLE N36°W 99.77', UTILITY POLE S19°W 49.13',
N33°E 77.58' TO SW CORNER OF BUILDING, S52°E 99.07' TO NW CORNER OF BUILDING.*
*L-13 55-34 & L-1 54-34 THE 1" IRON PIPE WITH BRASS CAP WITNESSED WITH SURVEY TAG NAILED TO:
POWER POLE N65°E 54.76', 6" RED PINE TREE S32°E 88.54',
POWER POLE S16°W 80.84', N03°E 48.75' TO SW CORNER OF STUCCO HOUSE.*

Signed by *Robert W. Crampton* Date Aug. 26, 1997
Surveyor's Michigan License No. 24591