

Ronald W. Haataja
Oct 28, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

For corners in
Houghton
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 55N R 34W
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

L-7

Mary Schoos 1P
Register of Deeds
Houghton County, Register
Page 1 of 1 LC 4/62
PAU Date 12/30/1999 Time 10:50:28
9. 000

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Ronald S. Haataja a field survey on March 16, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-7) North Quarter corner Section 24, T55N-R34W
40.24 Set Quarter Section post
References: Sugar 5" N19°W 6 lks.
Do 7" S20°E 16 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-7) North Quarter corner Section 24, T55N-R34W
Found 1 1/4" Round Iron Pin in Rock (pin stamped "1/4 S")



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-7) North Quarter corner Section 24, T55N-R34W
Accepted the 1 1/4" pin as the corner. Cemented a 2" Aluminum Sleeve over pin and cemented on a Brass Houghton County Remonumentation cap
Witnesses: Brass Tags PS#39478 nailed into side of trees
4" Ironwood N76°E 2.64'
7" W. Birch S25°W 10.34'
7" Ironwood S87°W 12.28'
9" Cedar N11°W 24.60'

Signed by Ronald S. Haataja
Surveyor's Michigan License No. 39478

Date October 20, 1999