

**JAN 09 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
HOUGHTON  
(County)

Located In:

Corner Code #

- 1. Public Land Survey            T 55N R 34W
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L-9

NANCY FENILI    09/23/97  
HOUGHTON COUNTY    14:33 #  
LC    3/ 425 PAU Fee:    9.00  
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. W. CRAMPTON, in a field survey on SEPTEMBER 8, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

*L-9 ORIGINAL POST OR ACCESSORIES NOT FOUND. 1/4 CORNER BETWEEN SECTION 24 & 25.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*L-9 FOUND 1/4" IRON PIN 3' SOUTH OF C/L OF ARCADIAN RD, REPLACED WITH 1/2" IRON PIPE WITH 2 1/4" BRASS CAP. PREVIOUSLY RECORDED BY BRIAN R. TAAVOLA IN LIBER 2, PAGE 545.*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*L-9 1/2" IRON PIPE WITH BRASS CAP, WITNESSED WITH SURVEY TAG NAILED TO: POWER POLE N24°W 32.85', WOOD FENCE POST N39°E 43.50', 10" POPLAR TREE S54°W 68.76', S56°E 81.84' TO NW CORNER BLOCK FOUNDATION OF HOUSE.*

Signed by Robert W. Crampton

Date Aug. 26, 1997

Surveyor's Michigan License No. 24591