

**JAN 09 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*SEPT 23, 1997*  
*Robert W. Crampton*  
For corners in  
HOUGHTON  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

**SECTION**

- |                                      |   |            |   |            |             |
|--------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey                | T | <u>55N</u> | R | <u>34W</u> | <u>L-11</u> |
|                                      | T | _____      | R | _____      | _____       |
|                                      | T | _____      | R | _____      | _____       |
|                                      | T | _____      | R | _____      | _____       |
| 2. Property Controlling in Section   | S | _____      | T | _____      | _____       |
|                                      | S | _____      | T | _____      | _____       |
| 3. Miscellaneous Property in Section | S | _____      | T | _____      | _____       |
|                                      | S | _____      | T | _____      | _____       |

NANCY FENILI 09/23/97 #  
 HOUGHTON COUNTY 14:33  
 LC 3/ 426 PAU Fee: 9.00  
 Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, R.W. CRAMPTON, in a field survey on OCTOBER 30, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

*L-11 S ¼ COR. SEC. 25, NOT SET IN ORIGINAL SURVEY, AREA ORIGINALLY A BAY OFF PORTAGE LAKE.*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

*L-11 S ¼ COR. SEC. 25, FOUND ¾" CAPPED PIPE, L.S. 24591, 7" BELOW GRADE, MDOT WITNESS: YELLOW PAINT DOT ON SLAG PILE S42W 59.03', REPLACED WITH ½" IRON PIPE WITH 2 ¼" BRASS CAP. PREVIOUSLY RECORDED BY BRIAN R. TAAVOLA, IN LIBER 2, PAGE 805.*



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

*L-11 S ¼ COR. SEC. 25, ½" IRON PIPE WITH BRASS CAP, WITNESSED WITH SURVEY TAG NAILED TO: ½" C. PIN, L.S. 13034 N00°04'30" E 162.80', ½" C. PIN, L.S. 13034 "R.M." N56°15' E 68.42', ½" C. PIN, L.S. 13034 "R.M." S21°55' E 68.50', P.K. NAIL IN SLAG PILE S44°29' W 59.30'.*

Signed by Robert W. Crampton  
 Surveyor's Michigan License No. 24591

Date Aug. 26, 1997