

Houghton County
Ronald W. Haataja
Oct 28, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000
SECTION

For corners in Houghton Located In: _____ Corner Code # _____
 (County)

- 1. Public Land Survey T55N R 34W M-7 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Mary Schoos IP
 Register of Deeds
 Houghton County, Register
 Page 1 of 1 LC 4/58
 PAU Date 12/30/1999 Time 10:46:32
 9.000
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Ronald S. Haataja, in a field survey on April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (M-7) SE Corner Section 13, T55N-R34W
 80.00 Set post corner of Sections 13 & 24
 References: Sugar 8" S15°W 31 lks.
 Do 14" N42°E 16 lks.

Great aberrations of the needle indicate presence of Trap Rock but not seen here.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (M-7) SE corner Section 13, T55N-R34W
 Found 1" o.d. pipe 25' South of Road centerline with witnesses by P.S. # 19833

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (M-7) SE corner Section 13, T55N-R34W
 Cemented on a Brass Houghton County Remonumentation cap

- Witnesses: P.S. # 19833
 3" Ironwood S80°E 12.18'
 12" Oak S02°E 26.68'
 8" Maple S42°W 22.05'
 6" Ash N35°W 57.89'



Signed by Ronald S. Haataja
 Surveyor's Michigan License No. 39478

Date October 20, 1999