

**SURVEY &  
REMONUMENTATION**

DEC 16 1996

*Re - Mon Liber 1, Page 28*

**COMMISSION  
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey Grant	T <u>15</u> N R <u>11</u> E	<u>B-13</u>
	T _____ R _____	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

30 OCT 96 9:46 A.M.

FRANCES L. HOLLOWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T15NR11E, 1835, Harvey Parke, D.S.

B-13: South ¼ Corner of Section 31  
Post  
Lynn 8", N45°W, 33 links  
B. Ash 14", N56°E, 23 links

No County Surveyor's Record, recorded surveys or LCRC

C-13: Corner of Sections 31 & 32  
Post  
Maple 8", N77½°E, 9½ links  
B. Ash 15", N30°W, 38 links

County Surveyors Record: ¼" iron  
Rowe Eng.: ¼" iron  
No recorded surveys or LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13: South ¼ Corner of Section 31

There is no remaining evidence of the original corner position

C-13: Corner of Sections 31 & 32

Found ¼" iron, 6" below grd.  
3' North of centerline Huron Line Rd.  
3' West of centerline Maxwell Rd.  
Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13: South ¼ Corner of Section 31

At proportionate distance,  
Set ½" iron w/cap #39089, 3" below grd.  
From which:  
Centerline of Huron Line Rd. bears, South, 1.0'  
Nail in Power Pole bears, North, 124.00'  
½" iron flush w/grd. bears N64°W, 27.3'  
½" iron flush w/grd. bears S60°W, 28.75'  
½" iron flush w/grd. bears S52°E, 23.5'

C-13: Corner of Sections 31 & 32

Set ½" iron w/cap #39089,  
3" below grd. over ¼" iron  
From which:  
Road sign post bears N52°W, 27.5'  
Nail in power pole bears N55°E, 38.5'  
Road sign post bears S61°E, 17.6'  
Yield sign post bears S72°W, 56.15'  
1¼" pipe, 3" below grd. bears West, 6.1'

Signed by James T. Meek Date \_\_\_\_\_  
Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 10-29-96  
RLB CSG gm

