

DEC 1 6 1996

COMMISSION

Re-Mon. Liber 1, Page 31

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in

| <u>Huron</u> (County) | Located in: | Corner Code # |
|------------------------------------|-----------------------------|---------------|
| 1. Public Land survey Grant | T <u>15 N</u> R <u>11 E</u> | <u>H-13</u> |
| | T _____ R _____ | <u>I-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |

30 OCT 96 9:47 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T15NR11E, 1835, Harvey Parke, D.S.

H-13 South ¼ Corner of Section 34
Post
Beech 20", N45½°E, 30 links
Hemlock 10", N82°W, 27 links

I-13 Corner of Sections 34 and 35
Post
Hemlock 30", N87°E, 34 links
Hemlock 10", N12°W, 36½ links

No county surveyors record, recorded surveys or LCRC

No county surveyors record, Rowe Eng.: 1¼" pipe
Liber 4, Page 689 HCR; 1¼" pipe
Liber 3, Page 63 HCR; 1¼" pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 South ¼ Corner of Section 34

Found 1" iron 2" below grd.
At centerline of Huron Line Rd.

Accepted as the best available evidence of original corner position

I-13 Corner of Sections 34 and 35

Found 1¼" pipe, 4" below grd.
At intersection Huron Line Rd. and Hartsell Rd

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South ¼ Corner of Section 34

Set ½" iron w/cap #39089, 3" below grd.
over 1" iron
At centerline of Huron Line Rd.
From which:
Nail in power pole bears S40°E, 81.7'
½" iron flush w/grd bears N52°E, 30.0'
½" iron flush w/grd bears N54°W, 30.0'
½" iron flush w/grd bears S56°W, 25.0'

I-13 Corner of Sections 34 and 35

Set ½" iron with cap #39089, 3" below ground
over 1¼" pipe
From which:
Nail in power pole bears N60°W, 83.3'
Road sign post bears N10°W, 33.3'
Road sign post bears S66°E, 95.9'
Buried Cable post bears South, 32.4'
1" pipe, 4" below grd. bears, East 49.1'

Signed by [Signature]
Surveyor's Michigan License No. 39089

Date 1996

APPROVED AT PEER BOARD MEETING, 10-29-96
KLB CSG JM

