

DEC 1 8 1996

COMMERCIAL

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

*Re-Mon. Liber 1, Page 31*

30 OCT 96 9:47 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For Corners in	Located in:	Corner Code #
<u>Huron</u> (County)		
1. Public Land survey Grant	T <u>15 N</u> R <u>11 E</u>	H-13
	T _____ R _____	<u>I-13</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T15NR11E, 1835, Harvey Parke, D.S.

<p>H-13 South 1/4 Corner of Section 34 Post Beech 20", N45 1/2°E, 30 links Hemlock 10", N82°W, 27 links</p> <p>No county surveyors record, recorded surveys or LCRC</p>	<p>I-13 Corner of Sections 34 and 35 Post Hemlock 30", N87°E, 34 links Hemlock 10", N12°W, 36 1/2 links</p> <p>No county surveyors record, Rowe Eng.: 1 1/4" pipe Liber 4, Page 689 HCR; 1 1/4" pipe Liber 3, Page 63 HCR: 1 1/4" pipe</p>
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<p>H-13 South 1/4 Corner of Section 34</p> <p>Found 1" iron 2" below grd. At centerline of Huron Line Rd.</p> <p>Accepted as the best available evidence of original corner position</p>	<p>I-13 Corner of Sections 34 and 35</p> <p>Found 1 1/4" pipe, 4" below grd. At intersection Huron Line Rd. and Hartsell Rd</p> <p>Accepted as the best available evidence of original corner position</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>H-13 South 1/4 Corner of Section 34</p> <p>Set 1/2" iron w/cap #39089, 3" below grd. over 1" iron At centerline of Huron Line Rd. From which: Nail in power pole bears S40°E, 81.7' 1/2" iron flush w/grd bears N52°E, 30.0' 1/2" iron flush w/grd bears N54°W, 30.0' 1/2" iron flush w/grd bears S56°W, 25.0'</p>	<p>I-13 Corner of Sections 34 and 35</p> <p>Set 1/2" iron with cap #39089, 3" below ground over 1 1/4" pipe From which: Nail in power pole bears N60°W, 83.3' Road sign post bears N10°W, 33.3' Road sign post bears S66°E, 95.9' Buried Cable post bears South, 32.4' 1" pipe, 4" below grd. bears, East 49.1'</p>
---	---

Signed by [Signature]  
Surveyor's Michigan License No. 39089

Date 10-29-96

APPROVED AT PEER BOARD MEETING, 10-29-96  
RLB CSG gm

