

DEC 16 1996

Re-Monumented, Page 33

COMMISSION
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Grant	T <u>15 N</u> R <u>11 E</u>	<u>L-13</u>
		T _____ R _____	M-13
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous	S _____	T _____ R _____	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

30 OCT 96 9:47 A.M.

FRANCES L. HOLIDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T15NR11E, 1835, Harvey Parke, D.S.

L-13 South ¼ Corner of Section 36
Post
Elm 16", N78°W, 17 links
Hemlock 24", N67½°E, 38 links

M-13 Corner of Townships 14 and 15 North,
Ranges 11 and 12 East
Post
Hemlock 24", N65°E, 31 links
Hemlock 28", S48°W, 59 links

No county surveyors record, recorded surveys or LCRC

No county surveyors record or recorded surveys
LCRC Recorded in Elkland Twp, Page 32 TCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36
Found ¾" iron 1½' below grd.
Centerline of Huron Line Rd. bears North, 1'
Accepted as the best available evidence of original corner position

M-13 Corner of Townships 14 and 15 North,
Ranges 11 and 12 East
Found 2" brass cap, 10" below grd.
At intersection of Huron Line Rd. and
Grassmere Rd.

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36
Set 'T' iron w/cap #39089, 3" below grd.
over ¾" iron
From which:
Nail in Power pole bears N3°W, 53.95'
½" iron, flush w/grd. bears N58°E, 37.0'
½" iron, flush w/grd. bears S54°E, 25.0'
½" iron, flush w/grd. bears S57°W, 25.0'

M-13 Corner of Townships 14 and 15 North,
Ranges 11 and 12 East
2" Brass cap, 10" below grd.
From which:
Huron County sign post bears N22°E, 61.7'
Nail & tag in 18" Birch bears S15°E, 94.8'
Nail & tag in power pole bears S45°W, 48.6'
½" iron flush w/grd. bears N15°W, 50.7'
½" iron flush w/grd. bears N20°E, 46.1'

Signed by James T. Meek

Date October 1996

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 10-29-96
RLB CSG gm

