

DEC 1 8 1996

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Re-Monument, Page 33

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Grant	T <u>15</u> N R <u>11</u> E	<u>L-13</u>
		T _____ R _____	<u>M-13</u>
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous	S _____	T _____ R _____	

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

30 OCT 96 9:47 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original survey South Bdy. T15NR11E, 1835, Harvey Parke, D.S.

L-13 South ¼ Corner of Section 36  
Post  
Elm 16", N78°W, 17 links  
Hemlock 24", N67½°E, 38 links  
  
No county surveyors record, recorded surveys or LCRC

M-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East  
Post  
Hemlock 24", N65°E, 31 links  
Hemlock 28", S48°W, 59 links  
  
No county surveyors record or recorded surveys  
LCRC Recorded in Elkland Twp, Page 32 TCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36  
  
Found ¾" iron 1½' below grd.  
Centerline of Huron Line Rd. bears North, 1'  
  
Accepted as the best available evidence of original corner position

M-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East  
  
Found 2" brass cap, 10" below grd.  
At intersection of Huron Line Rd. and Grassmere Rd.  
  
Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36  
  
Set 'T' iron w/cap #39089, 3" below grd. over ¾" iron  
From which:  
Nail in Power pole bears N3°W, 53.95'  
½" iron, flush w/grd. bears N58°E, 37.0'  
½" iron, flush w/grd. bears S54°E, 25.0'  
½" iron, flush w/grd. bears S57°W, 25.0'

M-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East  
2" Brass cap, 10" below grd.  
  
From which:  
Huron County sign post bears N22°E, 61.7'  
Nail & tag in 18" Birch bears S15°E, 94.8'  
Nail & tag in power pole bears S45°W, 48.6'  
½" iron flush w/grd. bears N15°W, 50.7'  
½" iron flush w/grd. bears N20°E, 46.1'

Signed by [Signature] Date 10-29-96  
Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 10-29-96  
RLB CSG JM  
5.11.11

