

DEC 1 6 1996

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Re-Mon. Likert, Page 34

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey: Sheridan	T <u>15 N</u> R <u>12 E</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

30 OCT 96 9:47 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey, South Bdy. T15NR12E, 1835, Harvey Parke D.S.

A-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East
Post
Hemlock 24", N65°E, 31 links
Hemlock 28", S48°W, 59 links

No County Surveyor's Record or recorded surveys
LCRC Recorded in Elkland Twp., Page 32 TCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East

Found 2" Brass Cap, 10" below grd.
At the intersection with Huron Line Rd. and Grassmere Rd.

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Corner of Townships 14 and 15 North, Ranges 11 and 12 East


2" Brass Cap, 10" below grd.

From which:

Huron County sign post bears N22°E, 61.7'
Nail & tag in 18" Birch bears S15°E, 94.8'
Nail & tag in power pole bears S45°W, 48.6'
1/2" iron flush w/grd. bears N15°W, 50.7'
1/2" iron flush w/grd. bears N20°E, 46.1'

Signed by *James T. Meek* Date 10-29-96
Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING 10-29-96
RLB CS9. 97



1996