

SURVEY & REMONUMENTATION

MAR 19 1997

1996

Re-Monumentation, Page 48

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Sharidan Township

<u>Huron County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>12E</u>	<u>H-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 4:07 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Russell L. Brown, in a field survey on Oct. 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1834 G.L.O., H. Parke D.S.
 Set quarter Section Post
 Sugar 9", N72E 25 Links
 Sugar, N70 1/2W 35 Links
 County Surveyors Records: NONE
 County Road Commission Records: NONE
 Act 74 L.C.R.C. NONE
 No surveys recorded or unrecorded found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of original corner found.
 Re-established corner position by proportionate measure from G.L.O. Notes, between I-13 and G-13 as best evidence of original corner position for H-13, corner falls in approximate centerline gravel road East and West, and fence row North and South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 South 1/4 Corner Section 34, T15N-R12E H-13
 Set 1/2" x 18" Steel Stake capped R.L.S. 24588
 WITNESSES:
 N45°W 41.72' to Notch in West End 18" C.M.P.
 S50°W 70.24' to P.K. Nail in Southeast Side Power Pole
 S45°E 28.91' to 1/2" x 18" Steel Stake capped RLS 24599
 N05°W 25.86' to Notch East End 18" C.M.P.



Signed by Russell L. Brown
 Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED AT MEETING 11-05-96. *[Signature]*