

SURVEY & REMONUMENTATION

MAR 19 1997

1996

Re-monumentation

Re-Monumentation, Page 52

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Sheridan Township

<u>Huron County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> N R <u>12</u> E	<u>L-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 4:08 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on Oct. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O., H. Parke D.S.
Set quarter Section Post
Beech 6", N73E 4 1/2 Links
Beech 5", N17 1/2W 4 Links

County Road Commission Records:
NONE

County Surveyors Records:
NONE

Act 74 L.C.R.C.
NONE

No surveys recorded or unrecorded found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No evidence of original corner or accessories found.

Re-established corner position by proportionate measure from G.L.O. Notes, between M-13 and K-13 as best evidence of original corner position for L-13 corner falls in approximate centerline gravel road East and West, and fence row North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner Section 31, T15N-R12E L-13
Set 1/2" x 18" Steel Stake capped R.L.S. 24588

WITNESSES:
S45°W 27.98' to 1/2" x 18" Steel Stake capped 24588
S45°E 32.18' to 1/2" x 18" Steel Stake Capped 24588
N40°E 39.91' to Notch in East End 12" C.M.P.
North 25.01' to Notch in West End 12" C.M.P.



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED
AT MEETING 11-05-96 [Signature]