

**SURVEY & REMONUMENTATION**

MAR 19 1997

*Re-Mon Liber 1, Page 53*

COMMISSION

1996

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Sheridan Township

|                                    |                   |               |
|------------------------------------|-------------------|---------------|
| <u>Huron County</u><br>(County)    | Located In:       | Corner Code # |
| 1. Public Land Survey              | T15N R12E         | M-13 ✓        |
|                                    | T15N R13E         | A-13          |
|                                    | T14N R12E         | M-01          |
|                                    | T14N R13E         | A-01          |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___           |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | ___           |

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
7 NOV 96 4:08 P.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

I, Russell L. Brown, in a field survey on Oct. 8, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below;

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 G.L.O., H. Parke D.S.  
Post Corner Townships 14 and 15N, Ranges 12 and 13 East  
Lynn 24", N58 1/2E 52 Links  
Beech 10", S67W 33 Links

County Road Commission Records:  
for Bingham Township 31 Southwest, T15N-R13E  
1/2" Iron Pipe, Replaced with 3/4" Iron Pin  
Spike in Power Pole, N55°E 63.85'  
Spike in Telephone Pole, S45°E 70.85'  
Spike in Telephone Pole, N45°W 52.30'

County Surveyor Records:  
NONE  
(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1" Pipe in Monument Box, centerline Asphalt road North and South, centerline gravel road West, and 6'+ North centerline gravel road East.

Accepted: Found 1" pipe in Monument Box as the best evidence of the original position of Corner M-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Southeast Corner Section 36, T15N-R12E M-13  
Found 1" Pipe in Monument Box

WITNESSES:  
N45°W 57.69' to 1/2" Dia. Steel Stake capped RLS 24588  
S45°W 72.90' Eound Form Nail and Flasher in Northwest Side of Power Pole  
S30°E 62.63' to 1/2" Dia. Steel Stake capped RLS 24588  
N45°E 63.93' Found P.K. Nail in Northwest Side Power Pole

This Corner is common with M-1 T14N-R12E, A-13 T15N-R13E, and A-1 T14N-R13E.



Surveyed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED [Signature]  
AT MEETING 11-05-96

*Liber 1, Page 53A*

County Road Commission Records for Sheridan Township, 36 Southeast, T15N-R12E.  
Iron Pipe  
Spike in Power Pole, N55°E 63.85'  
Spike in Telephone Pole, S45°E 70.85'

November 10, 1992 - Act 74 L.C.R.C. Liber 1, Page 102, Huron County Records.  
Southwest Corner Section 31, (A-13) T15N-R13E.  
1" Pipe in Monument Box  
S52°W 72.92' to N and S in Power Pole  
N45°W 53.00' to 1/2" Re-Bar  
N64°E 63.95' to N in Power Pole

No surveys recorded or unrecorded found.