

**SURVEY &  
REMONUMENTATION**

MAR 19 1997

*Re-Mon Liber 1, Page 55*

COMMISSION

1996 REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bingham Township

<u>Huron County</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>13E</u>	<u>B-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
7 NOV 96 4:08 P.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Russell L. Brown, in a field survey on Oct. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O., H. Parke D.S.  
Set quarter Section Post  
Hemlock 10", N72E 37 Links  
Hemlock 8", N26W 22 Links

County Road Commission Records:  
NONE

November 10, 1992 Act 74 L.C.R.C. Recorded in  
Liber 1, Page 102 Huron County Records  
1/2" Re-Bar cap "JHM" 27456.  
N78°E 81.05' to Nail in 15" Poplar Tree  
N59°W 36.80' to 1/2" Rod  
S84°W 36.97' to 1/2" Rod  
West 5.87' Found 1/2" Re-Bar

County Surveyor Records:  
NONE

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Due to recent road reconstruction, monument and all accessories stated in Section A, above appear to have been destroyed.

Re-established Corner position by single proportionate measure between A-13 and C-13 as best evidence of original Corner position for B-13. Corner falls in approximate centerline gravel road East and West, and fence row to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner Section 31, T15N-R13E B-13  
Set 1/2" x 18" Steel Stake, capped R.L.S. 24588

WITNESSES:

- N45°W 22.99' to 1/2" x 18" Steel Stake capped RLS 24588
- N45°E 18.52' to 1/2" x 18" Steel Stake capped RLS 24588
- S45°E 22.32' to 1/2" x 18" Steel Stake capped RLS 24588
- S45°W 24.96' to 1/2" x 18" Steel Stake capped RLS 24588



Signed by Russell L. Brown

Date 11-05-96

Surveyor's Michigan License No. 24588

PEER GROUP APPROVED  
AT MEETING 11-05-96.

*[Handwritten signatures]*

*Liber 1, Page 55A*

July 2, 1992 Survey by Sheridan Surveying Company (Job No. 9206. 351).  
Same monument and accessories as November 10, 1992, Act 74 L.C.R.C. Liber 1, Page 102  
Huron County Records.

\$ 2.00 MSSR  
\$ 9.00 SURVEY