

**SURVEY &
REMONUMENTATION**

MAR 19 1997

COMMISSION 1996

Re-Mon Liber 1, Page 60
REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Bingham Township

<u>Huron County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> N R <u>13</u> E	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 4:09 P.M.
FRANCES L. HOLWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Russell L. Brown, in a field survey on Oct. 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O., H. Parke D.S.	County Road Commission
Set Post Corner Sections 33 and 34	2" Iron Pipe, Set and established by S.H. Department
Beech Tree 30", N86°W 16 Links	Nail and Tag in Corner Fence Post, N62°E 44.94'
Hemlock 12", N58 1/2°W 8 Links	Nail and Tag in Corner Fence Post, S45°W 38.75'
County Surveyor Records:	Nail and Tag in 6" Apple Tree, S46°E 52.62'
NONE	Nail and Tag in 20" Apple Tree, N40°W 56.62'
(OVER)	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat Spike in Monument Box in asphalt apron 14.80 feet West of Centerline M-19 and in line Centerline gravel road East and West.

Accepted: Found Boat Spike in Monument Box as the best evidence of the original Corner position of Corner G-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner Sections 33 and 34, T15N-R13E G-13
Found Boat Spike in Monument Box, 14.80' West Centerline M-19 in Line Centerline Gravel Road East and West.
N55°W 75.75' to Spike in Southwest Side Power Pole
S55°W 71.73' to Spike in Southeast Side Power Pole
S65°E 69.92' to Southwest Corner of Concrete Headwall
N65°E 69.06' to Northwest Corner of Concrete Headwall



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED
AT MEETING 11-05-96
[Signatures]

Liber 1, Page 60A

Act 74 Forms
NONE

Survey, Liber 1, Page 486, Huron County Records
Monument Box
Spike in Southeast Side, Power Pole, S55°W 71.40'
Spike in Northeast Side, Power Pole, N50°W 75.73'
Spike in Southwest Side of Telephone Pole S70°E 92.75'

M.D.Q.T. Construction Plans State Trunkline M-19, dated April 58
Corner Sections 3 and 4, T14N-R13E
Found 3/4" Pipe
N49°W 70.49' to 20" Apple Tree
N40°E 34.13' to 12" Elder
S33°E 34.66' to Telephone Pole
S55°W 56.75' to Post

\$ 2.00 MSSR
\$ 9.00 SURVEY