

SURVEY & REMONUMENTATION

MAR 19 1997

Re-Mon Liber 1, Page 61

COMMISSION¹⁹⁹⁶ REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bingham Township

<u>Huron County</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>15</u> N R <u>13</u> E	H-13	
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		

STATE OF MICHIGAN
HURON COUNTY
RECORDED

7 NOV 96 4:09 P.M.

FRANCES L. HOLWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on Oct. 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O., H. Parke D.S.	County Road Commission Records
Set quarter Section Post	Old Cedar Post, Iron Pipe
B. Ash 26", N91/2°W 4 Links	Nail and Tag in Corner Fence Post S44°E 39.98'
B. Ash 16", N60 1/2°E 34 1/2 Links	Nail and Tag in Corner Fence Post N04°W 28.48'
County Surveyor Records	Spike in Corner Post, South 42.05'
NONE	Spike in Corner Post, S45°E 54.80'
ACT 74 Form: NONE	Spike in Post, N09°W 28.48'
	Recorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Steel Stake Approximate. Centerline of gravel road East and West, 3" below surface.

Accepted: Found 3/4" Steel Stake as the best evidence of the original corner position of Corner H-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner Section 34, T15N-R13E H-13
Found 3/4" Steel Stake, 3" ± below Surface, 3'± North of Centerline gravel road East and West

WITNESSES:
 N15°W 45.10' to Spike in East Side of 14" Elm Tree
 S45°W 31.11' to 1/2" Dia. Steel Stake Capped R.L.S. 24588
 S45°E 34.18' to 1/2" Dia. Steel Stake Capped R.L.S. 24588
 N60°E 41.78' to 1/2" Dia. Steel Stake Capped R.L.S. 24588



Signed by Russell L. Brown
 Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED
 AT MEETING 11-05-96 *[Signatures]*