

**SURVEY &
REMONUMENTATION**

MAR 19 1997

COMMISSION

1996

REMONUMENTATION

Re-New Link 1, Page 62

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bingham Township

Huron County (County)	Located in:	Corner Code #
1. Public Land Survey	T15N R13E	I-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 4:09 P.M.
FRANCES L. HOLWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on Oct. 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O., H. Parke D.S.
Set Post Corner Sections 34 and 35
B. Ash 10", N65E 24 1/2 Links
Birch 5", N67W 18 12 Links

County Road Commission Record:
Axle in Cedar Post in Center of grades to North, East And West
Spike in 14" Ash, N45°E 61.75'
Corner Fence Post, Northwest 38.0'

County Surveyor Records:
NONE

Act 74 Form:
NONE

Recorded Surveys; NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Steel Stake in Centerline gravel roads North, East and West, 24" below surface.

Accepted: Found 3/4" Steel Stake as best evidence of original Corner position for Corner I-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner Sections 34 and 35, T15N-R13E I-13

Found 3/4" Steel Stake, raised to 4" below surface with 1" Steel Pipe and R. L. Brown Cap 24588

WITNESSES:

- N40°W 39.87' to Notch West End 36" C.M.P.
- N45°W 38.47' to Notch North End 36" C.M.P.
- S45°W 33.85' to Notch South End 36" C.M.P.
- S55°E 74.38' to Spike in Southwest Side 12" Poplar Tree
- N45°E 39.43' to Notch East End 36" C.M.P.



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date 11-05-96

PEER GROUP APPROVED
AT MEETING 11-05-96