SURVEY & REMONUMENTATION

MAR 1 9 1997

COMMISSION

PEER CROUP APPROVED AT MEETING 11-05-96

Re-Man Lile 1, Page 64 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bingham Township Filing Requirement of Act 74, Mich. I	P.A. 1970
Huron County Located In: Corner Code #	STATE OF HICHIGAN
1. Public Land Survey T 15N R 13E K-13 T R	HURON COUNTY RECORDED
2. Property Controlling S T R	7 NOV 96 4:10 P.H.
in Section S T R 3. Miscellaneous S T R Property in Sec. S T R	FRANCES L, HOLDWICK REGISTER OF DEEDS
4 Lat Na	Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat 5. Private Claims	ABCDEFGHIJKI
	2 6 5 4 3 2
I, Russell L. Brown, in a field survey on Oct. 7, 19 96 do hereby state that	3
 conformance with regulations and rules therefore are confirmed by the mentioned in lines 1 and 2 above w 	ere in
that the corner points mentioned in lines 3, 4 and 5 Editu Management or by a decree of a Court of Law ar	nd /or 6 12 12 1
Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monume recovered, found as expressed below:	nted,
NOTE: Not more than 2 corners, all in the same town and range, may be recorded	8 19 20 21 22 23 24
on this certificate.	10 30 29 28 27 26 25
	11 32 33 34 36 36
A. Description of original monument and accessories and/or subsequent restoration: 1834 G.L.O., H. Parke D.S. 1883 Dungan M	13
Sot Boot Commen C	tion 36, Tl5N-R13E. shed Post
County Road Commission Records: County Surveyor 5/8" Steel Pin in center of grades NONE Corner fence post, N50°E 53.80'	ors Records:
Act 74 Forms:	
B. Description of corner evidence found and/or method applied in restoring or reestablishing	corner:
Found 3/4" Steel Stake in centerline intersection gravel r	roads North, West and East, in Fig.
Accepted: Found 3/4" Steel Stake as best evidence of origi	nal position of Corner K-13.
Description of monument for corner and accessories established to perpetuate locating the Corner Section 35 and 36, T15N-R13E K-13	position of the corner:
Found 3/4" Steel Stake WITNESSES: N45°W 54.10' to 1/2" Dia Steel Stake Capped RLS 24588	TE OF MICHIGAN
S50°W 80.19' to Spike in Southeast Side of 10" Twin Thornay S60°E 35.33' to 1/2" Dia Steel Stake capped RLS 24588 N45°E 58.32' to 1/2" Dia. Steel Stake capped RLS 24588	LAND
O CONTROL CAPPER RLS 24588	SURVEYOR ON NO. 24588
igned by Mall & Chocan	1-05-90 LAND SUR
-urveyor's Michigan License No. 24588	