

*Common to A13 - Sigel Twp. - T16N-R14E
 *Common to M13 - Verona Twp. - T16N-R13E
 *Common to M01 - Bingham Twp. - T15N-R13E

SURVEY & REMONUMENTATION

Re-Mon. Lieberl, Page 100

1997 REMONUMENTATION

JAN 22 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **PARIS TOWNSHIP**

HURON SECTION
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>15</u> N R <u>14</u> E	<u>A-1</u> ✓
	T <u>16</u> N R <u>14</u> E	<u>A-13</u>
	T <u>15</u> N R <u>13</u> E	<u>M-1</u>
	T <u>16</u> N R <u>13</u> E	<u>M-13</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED
 1 DEC 97 1:53 P.M.
 FRANCES L. HOLDWICK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Russell L. Brown, in a field survey on Oct. 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


1834 G.L.O. H. Parke D.S. Intersected Range Line 1.39 South of Temporary Township Cor. Post Beech 12 S53E 11, Ironwood 8 N54 1/2W 13,
 COUNTY SURVEYOR RECORDS: None
 ACT 74 FORM: None
 COUNTY ROAD COMMISSION RECORDS: None
 RECORDED SURVEYS: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.
 Found 3/4" Steel Stake in Monument Box
 Accepted 3/4" Steel Stake in Monument Box as the best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

N.W. Corner Section 6, T15N-R14E, A-1
 Found 3/4" Steel Stake in Monument Box
 WITNESSES:
 N45°E 54.85' to P.K. Nail in Power Pole
 N45°W 35.09' to V Notch in West End C.M.P.
 S60°W 92.47' to P.K. Nail in Power Pole
 S60°E 32.56' to 1/2" x 18" Steel Stake
 East 2751.57' to South 1/4 Corner Section 31, T16N-R14E
 West 2636.57' to South 1/4 Corner Section 36, T16N-R13E
 This corner is common with A-13, T16N-R14E, M-13, T16N-R13E, and M-1, T15N-R13E



Signed by Russell L. Brown
 Surveyor's Michigan License No. 24588

Date Nov. 3, 1997

PEER GROUP APPROVED
 AT MEETING HELD
Nov. 25, 1997. RLB