

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

REMONUMENTATION

*Re-Monumentation, Page 15*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Paris T15NR14E	A-13, B-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
10 SEP 96 8:41 A.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-13 GLO Notes Intersected Range Line  
Set Post at 81.06 Chains  
Beech 11", S11°W, 14 Links  
Do. 16", N23-1/2°E 31 1/2 Links  
County Surveyor's Record - None, Act 74 - None, Act 132 - None, Unrecorded Survey dated 8-30-95 by Huron Surveying, Inc.
- B-13 GLO Notes  
Set 1/4 Post at 40.00 Chains  
Beech 24", N64°E, 25 Links  
Do. 20", N40°W, 35 Links  
County Surveyor's Record - None, Act 74 - None, Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 SW Cor, Section 31, T15N-R14E  
Found 1/2" Iron Bar in Centerline of Gravel Road (Intersection of Huron Line Road and Verona Road)  
APPROVED PEER BOARD MEETING  
Sept. 9, 1996  
*RLB*

B-13 S 1/4 Cor, Section 31, T15N-R14E  
Found No Evidence of an Existing Corner at site, (Huron Line Road). Set 1/2" Iron Bar on straight line, using GLO proportion, between SE Cor, Section 31, T15N-R14E and SW Cor, Section 31, T15N-R14E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-13 SW Cor, Section 31, T15N-R14E  
1/2" Iron Bar in Gravel Road Bed  
N45°E 70.75' to Nail in SE Side of Anchor Pole  
S45°E 44.05' to Nail in NE Side of Power Pole  
N45°W 72.47' to Nail in NE Side of Power Pole  
S45°W 49.80' to Nail in SE Side of Anchor Pole  
East 2716.65' to S 1/4 Cor, Sec 31, T15N-R14E
- B-13 S 1/4 Cor, Section 31, T15N-R14E  
1/2" Iron Bar in Gravel Road Bed  
East 33.67' to 1/2" Iron Bar in Gravel Road Bed  
North 36.05' to Nail in E. Side of Fence Post  
N40°E 37.35' to Nail in 6" Willow  
S40°E 76.80' to Nail in Clump of Apple Trees  
West 2716.65' to SW Cor, Sec 31, T15N-R14E  
East 2646.51' to SE Cor, Sec 31, T15N-R14E

Signed by Charles S. Getz Date July 15, 1996  
Surveyor's Michigan License No. 25843

