

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

REMONUMENTATION

Re-Monumentation, Page 15

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Huron
(County)

Located In: Paris
Corner Code # A-13, B-13

1. Public Land Survey	T <u>15</u> N <u>R14</u> E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
10 SEP 96 8:41 A.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 GLO Notes Intersected Range Line
Set Post at 81.06 Chains
Beech 11", S11°W, 14 Links
Do. 16", N23-1/2°E 31 1/2 Links

County Surveyor's Record - None, Act 74 - None,
Act 132 - None, Unrecorded Survey dated 8-30-95
by Huron Surveying, Inc.

B-13 GLO Notes
Set 1/4 Post at 40.00 Chains
Beech 24", N64°E, 25 Links
Do. 20", N40°W, 35 Links

County Surveyor's Record - None, Act 74 - None,
Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 SW Cor, Section 31, T15N-R14E
Found 1/2" Iron Bar in Centerline of
Gravel Road (Intersection of Huron Line
Road and Verona Road)

APPROVED PEER BOARD MEETING
Sept. 9, 1996
RLB

B-13 S 1/4 Cor, Section 31, T15N-R14E
Found No Evidence of an Existing Corner at site, (Huron Line Road). Set 1/2" Iron Bar on
straight line, using GLO proportion, between SE Cor, Section 31, T15N-R14E and SW Cor,
Section 31, T15N-R14E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 SW Cor, Section 31, T15N-R14E
1/2" Iron Bar in Gravel Road Bed
N45°E 70.75' to Nail in SE Side of Anchor Pole
S45°E 44.05' to Nail in NE Side of Power Pole
N45°W 72.47' to Nail in NE Side of Power Pole
S45°W 49.80' to Nail in SE Side of Anchor Pole
East 2716.65' to S 1/4 Cor, Sec 31, T15N-R14E

B-13 S 1/4 Cor, Section 31, T15N-R14E
1/2" Iron Bar in Gravel Road Bed
East 33.67' to 1/2" Iron Bar in Gravel Road Bed
North 36.05' to Nail in E. Side of Fence Post
N40°E 37.35' to Nail in 6" Willow
S40°E 76.80' to Nail in Clump of Apple Trees
West 2716.65' to SW Cor, Sec 31, T15N-R14E
East 2646.51' to SE Cor, Sec 31, T15N-R14E

Signed by Charles S. Getz Date July 15, 1996
Surveyor's Michigan License No. 25843

