

**SURVEY &  
REMONUMENTATION**

REMONUMENTATION

*Re-Man Liber 1, Page 19*

OCT 29 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Paris T <u>15N</u> R <u>14E</u>	<u>C-13, D-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
10 SEP 96 8:42 A.M.  
FRANCES L. HOLDWICK  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13 GLO Notes  
Set Post at 80.00 Chains  
Beech 7", N11°E, 42 Links  
Hemlock 8", N60°W, 1 1/2 Links  
County Surveyor's Record - None, Act 74 - None, Act 132 - None
- D-13 GLO Notes  
Set 1/4 Post at 40.00 Chains  
Beech 12", N11°E, 1 Link  
Hemlock 11", N40°W 15 Links  
County Surveyor's Record - None, Act 74 - None, Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13  
SW Cor, Section 32, T15N-R14E  
Found 1/2" Iron Bar in Centerline of Gravel Road (Huron Line Road), 33.66' West of 1/2" Iron Bar in C of Huron Line Road & Maurer Road to South  
APPROVED PEER BOARD MEETING  
RLB Sept 9, 1996
- D-13  
S 1/4 Cor, Section 32, T15N-R14E  
Found No Evidence of an Existing Corner at site, (Huron Line Road). Set 1/2" Iron Bar on straight line at half distance between SE Cor, Section 32, T15N-R14E and SW Cor, Section 32, T15N-R14E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13  
SW Cor, Section 32, T15N-R14E  
1/2" Iron Bar in Gravel Road Bed  
East 33.66' to 1/2" Iron Bar in Gravel Road Bed  
S15°W 53.84' to Nail in NW Side of Power Pole  
N45°E 43.80' to West Leg of Road Sign  
S50°E 59.00' to Stop Sign  
West 2646.51' to S 1/4 Cor, Sec 31, T15N-R14E  
East-2637.65' to S 1/4 Cor, Sec 32, T15N-R14E
- D-13  
S 1/4 Cor, Section 32, T15N-R14E  
1/2" Iron Bar in Gravel Road Bed  
S50°W 83.68' to Nail in N. Side of Power Pole  
S70°W 148.50' to Nail in N. Side of 18" Pine  
S50°E 59.00' to Nail in N. Side of Fence Post  
West 2637.65' to SW Cor, Sec 32, T15N-R14E  
East 2637.65' to SE Cor, Sec 32, T15N-R14E

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date July 15, 1996

