

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

*Re-Mon Liber 1, Page 20*

**REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Paris T15N R14E	E-13, <u>F-13</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

10 SEP 96 8:42 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-13 GLO Notes  
Set Post at 80.00 Chains  
Sugar 31", N11°W, 41 Links  
Beech 7", N51°E, 30 Links  
County Surveyor's Record - Iron Pin replacing 8" Sq. Stone, Act 74 - None, Act 132 - Liber 4, Page 160, Unrecorded Survey dated 9-26-89 by Huron Surveying, Inc.
- F-13 GLO Notes  
Set 1/4 Post at 40.00 Chains  
Maple 11", N12-1/2°E, 13 Links  
Hemlock 7", N61°W, 20 1/2 Links  
County Surveyor's Record - None, Act 74 - None, Act 132 - Liber 4, Page 160

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13  
SW Cor, Section 33, T15N-R14E  
Found 1/2" Iron Bar in Centerline of Gravel Road (Intersection of Huron Line Road and Mac Donald Road), 46.86' West of 1" Bar in  $\frac{1}{2}$  of Huron Line Road & Gravel Road to South  
APPROVED PEER BOARD MEETING  
RUB Sept 9, 1996

F-13  
S 1/4 Cor, Section 33, T15N-R14E  
Found 5/8" Iron Bar in Gravel Road Bed (Huron Line Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13  
SW Cor, Section 33, T15N-R14E  
1/2" Iron Bar in Gravel Road Bed  
East 46.86' to 1" Bar in Gravel Road Bed  
S20°W 53.06' to Nail in NW Side of Power Pole  
S60°E 96.01' to Nail in N. Side of Telephone Pole  
North 17.10' to East Leg of Road Sign  
West 2637.65' to S 1/4 Cor, Sec 32, T15N-R14E  
East 2639.52' to S 1/4 Cor, Sec 33, T15N-R14E
- F-13  
S 1/4 Cor, Section 33, T15N-R14E  
5/8" Iron Bar in Gravel Road Bed  
N45°W 102.54' to Nail in S. Side of Power Pole  
S50°W 102.68' to Nail in N. Side of Telephone Pole  
South 67.50' to Nail in W. Side of 12" Ash  
West 2639.52' to SW Cor, Sec 33, T15N-R14E  
East 2651.36' to SE Cor, Sec 33, T15N-R14E

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date July 15, 1996

