

SURVEY &
REMONUMENTATION

OCT 29 1996

COMMISSION

REMONUMENTATION

Re-Monument, Page 16

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Paris T <u>15</u> N R <u>14</u> E	<u>I-13</u> , J-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

10 SEP 96 8:41 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-13 GLO Notes
Set Post at 80.00 Chains
Sugar 20", N75°W, 11 Links
Sugar 16", N30°E, 15 Links
County Surveyor's Record - Large Rock just .55 North of Ford Axle, Act 74 - None, Act 132 - None
- J-13 GLO Notes
Set 1/4 Cor at 40.00 Chains
Elm 7", N40°E, 3 Links
Hemlock 7", N13°W, 91 Links
County Surveyor's Record - 3/4" Iron Pin 1.0 North of Large Stone, Act 74 - None, Act 132 - None, Unrecorded Survey dated 5-23-95 by Case Surveying

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13
SW Cor, Section 35, T15N-R14E
Found Monument Box in Asphalt Road (Intersection of Huron Line Road and Parisville Road)
APPROVED PEER BOARD MEETING
RLB Sept 9, 1996
- J-13
S 1/4 Cor, Sec 35, T15N-R14E
Found Railroad Spike, 6" Deep, in Gravel Road Bed (Huron Line Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>I-13
SW Cor, Section 35, T15N-R14E
Mounment Box in Asphalt Road
West 20.46' to Mounment Box
S50°W 52.75' to Road Sign
S45°E 42.92' to Concrete Project Marker
N45°W 56.40' to Concrete Project Marker
West 2638.76' to S 1/4 Cor, Sec 34, T15N-R14E
East 2642.46' to S 1/4 Cor, Sec 35, T15N-R14E</p> | <p>J-13
S 1/4 Cor, Section 35, T15N-R14E
Railroad Spike in Gravel Road Bed
North 53.65' to Nail in E. Side of Power Pole
N30°W 40.90' to West End of 24" C.M.P.
North 198.83' to Nail in E. Side of 24" Ash
West 2642.46' to SW Cor, Sec 35, T15N-R14E
East 2610.50' to SE Cor, Sec 35, T15N-R14E</p> |
|--|---|

Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date July 15, 1996

